


Existing AB-FAT(F-ADC 579) is located at # 15 Chislehurst St



AB-FAT	AB-FAT Fibres	IFDB	IFDB Fibres	Lot No	Address
F-ADC 579	57..58	F-BEV 140	1..2	16A	Chislehurst St
F-ADC 579	59..60	F-BEV 140	3..4	18	Chislehurst St
F-ADC 579	61..62	F-BEV 140	5..6	18A	Chislehurst St
F-ADC 579	63..64	F-BEV 140	7..8	20	Chislehurst St
F-ADC 579	65..66	F-BEV 140	9..10	20A	Chislehurst St

Points	Codes	Fibre Joining
2	IC14a.1 x 1 MB02.1 x 1	Supply and Install Pedestal and IFDB(F-BEV 140)
	706 x 1 C14 x 1 758a x 1	Blow 12F EPFU from AB-FAT(F-ADC 579) is located at # 15 Chislehurst St to the new IFDB(F-BEV 140)
F-BEV 140 F-ADC 579 : 57-66 F-ADC 579/BIU 639		

Points	Codes	Civil
1	C12M x 1	Connect 1 x Ruggedized at the Drop off(Tube: 32)
1-2	D01 x 23.4 D03 x 22	ISB. Trench 23.4m in Grass MT 22m in Concrete and lay 1 x Ruggedized
2		Leave 1 x Ruggedized(Tube : 32) where a new IFDB (F-BEV 140) will be installed
2-3	D01 x 3	From IFDB (F-BEV 140) Trench 3m in Grass and lay 1 x Ruggedized
3		Leave a drop off for # 20A Chislehurst St
2-4	D01 x 8	From IFDB (F-BEV 140) Trench 8m in Grass and lay 1 x Ruggedized
4		Leave a drop off for # 20 Chislehurst St
2-5	D03 x 3	From IFDB (F-BEV 140) MT 3m in Concrete and lay 3 x Ruggedized
5		Leave drop off's for # 18 & # 18A Chislehurst St
5-6	D01 x 11	Trench 11m in Grass and lay 1 x Ruggedized
6		Leave a drop off for # 16A Chislehurst St